


**NOTE:**  
CONTRACTOR SHALL COORDINATE WITH ALL APPLICABLE CODES AND AGENCIES BY ALL APPLICABLE ORDINANCES/REGULATIONS, INCLUDING, BUT NOT LIMITED TO, APPLIED FOR ALL NECESSARY PERMITS, PRIOR TO CONSTRUCTION.

**NOTE:**  
PROPOSED SIDEWALK TO BE AT INSTALLED AT EXISTING GRADE AND MEET ALL UTILITY COVERING ELEVATION. CONCRETE CURB HEIGHT MAY VARY.

**NOTE:**  
CUSTOM OVERHEAD ARCHWAY AND CUSTOM BIKE RACK WILL BE PROVIDED BY OTHERS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THE INSTALLATION OF THESE ITEMS. FOR BIDDING PURPOSES, THE CONTRACTOR SHALL ASSUME THE CUSTOM OVERHEAD ARCHWAY WILL BE 8' LONG, STEEL MATERIAL, HAVE TWO (2) CONCRETE FOUNDATIONS, AND NEED ALL NECESSARY HARDWARE. THE CUSTOM OVERHEAD ARCHWAY WILL BE 11.25' LONG (CENTER OF COLUMN - CENTER OF COLUMN), A MINIMUM OF 7' ABOVE GRADE, STEEL MATERIAL, HAVE TWO (2) CONCRETE FOUNDATIONS, AND NEED ALL NECESSARY HARDWARE, AS SHOWN ON THE DETAILS. THE CONTRACTOR SHALL COORDINATE WITH OWNER AND/OR DESIGNER DURING THE SHOP DRAWING SUBMITTAL PHASE.

**NOTE:**  
CONTRACTOR TO ALLOW A MINIMUM OF TWO (2) WEEKS DRYING TIME AFTER POWER WASHING WALLS BEFORE COMPLETING ANY REPAIRS OR PAINTING.



- CONSTRUCT**
- 1 LS Floor Wash Band Shell Building, including concrete steps and walls including concrete steps, stage floor, and interior walls, including but not limited to sanding and an exterior painted finish
  - 116 SF Concrete Vertical Curb, including 2" wide, 4.8' depth, roadway restoration concrete sidewalk, 4" thick
  - 124 SF Concrete Paver Sidewalk, including sub-base
  - 53 SF Cast Stone Concrete Block Sidewalk, with top, 20" high
  - 2 LF Cast Stone Concrete Block Pillar, with top, 33" high
  - 1 LS Double Sided LED Display Sign, including poles, cross braces, mounting hardware, concrete foundations, and electrical connections
  - 1 LS Custom Overhead Archway Installation Only, including concrete foundations
  - 1 UN Industrial Grade Steel Pole, 8" dia., 20' high, including concrete foundation
  - 2 UN Decorative Trash Receptacle, 6' long, including surface mount anchoring and concrete pad (6' x 2')
  - 4 LB Backless Bench, 6' long, including surface mount anchoring and concrete pad (6' x 2')
  - 2 LB Decorative Trash Receptacle, including surface mount anchoring and pad (6' x 2')
  - 2 UN Custom LED Sign, including concrete foundations and pad (6'0"x7')
  - 2 LB Wall Mounted Collecting Fan
- CONSTRUCT (ADD 'A')**
- 1 LS Remove and Replace LED Display Sign, including cross braces, mounting hardware, and electrical connections

NO.	DESCRIPTION OF REVISION	DATE	BY	DRWN	CHKD
BOROUGH OF PALMYRA BURLINGTON COUNTY, NEW JERSEY <b>IMPROVEMENTS TO GROVE PARK            BLOCK 28, LOT 3</b> SITE PLAN					
 <b>GREGORY R. VAYNSKY, P.P.E., INC.</b> CONSULTING AND MUNICIPAL ENGINEERS <small>FOR BIDDING PURPOSES ONLY - NOT TO BE USED FOR CONSTRUCTION</small>					
JENNIFER ALFARO, P.E.	DANIELA DAMALAZA, P.E.	JONATHAN STEINBERG, L.S. P.E.			
JANIS CORNELIUS, P.E.	MICHAEL W. INGLELAND, P.E., P.S.	GREGORY WELSH, P.E., P.S.			
SCALE: 1" = 10' DATE: JUN 2010			SHEET NO.	DRAWING NO.	PROJECT NO.
NEW JERSEY PROFESSIONAL ENGINEERING BOARD - N.J.L.C. 34456			DATE: JUN 2010	SHEET NO.	PROJECT NO.

